

Pre-Test Checklist

Further to carrying out on site testing, Salveo Solutions can offer advice over the telephone prior to tests being carried out to improve air pressure testing performance.

- We require two 110/240v Electric sockets provided by site
- Ensure the building envelope is complete. all Glazing, External doors and cladding to be complete
- Light fixtures to be fitted
- All sockets to be fitted
- Any penetration made through the external envelope to be sealed
- Any loft/storage doors, hatches, to be finished and in place with a draft excluder
- SVP and any waste pipes passing through the external walls and ceilings to be sealed
- If applicable all boxing in housing a soil pipe, to be sealed if exiting through the ceiling or external wall
- Plumbing installed and all traps to have water in
- Skirting board to be in fixed and sealed top and bottom
- If you have a chimney please make sure this has already been sealed prior to our visit, everything else we seal, including extractor fans and trickle vents

For **FREE** advice and to get a fast quote please call us on **07507 456005**